

MODEL #8300

## 12' Intermediate Duty Main Beam



MODEL #8300

# 12' Intermediate Duty Main Beam

12' Intermediate Duty Main Beam



## Installation Method

Suspended/Drop (accessibility)



## Fire Guard

Yes

---

## Residential Fire Safety

This grid component, with certain Armstrong ceilings, also complies with the I-Joist Floor Fire Safety Code, being adopted in more and more states.





---

## Installation


Read the detailed installation instructions before starting your project.

# Details

<b>Model Number</b>	8300
<b>Product Name</b>	12' Intermediate Duty Main Beam
<b>Component</b>	Main Beam
<b>Installation Method</b>	 Suspended/Drop (accessibility)
<b>Collection</b>	<u><a href="#">PRELUDE XL 15/16" Fire Guard Grid System</a></u>
<b>Color</b>	Tech Black
<b>Duty Rating</b>	Intermediate Duty
<b><u>Fire Guard</u></b>	 Yes
<b>Length</b>	144"
<b>Height</b>	1-11/16"
<b>Material Type</b>	Hot-dipped Galvanized Steel

<b>End Detail</b>	Staked-on clip (SuperLock)
<b>Product Type</b>	Installation Systems

## Resources

PDF <b>BROCHURE - FIRE SAFETY</b> 114K
PDF <b>INSTALLATION INSTRUCTIONS - FIRE GUARD CEILINGS AND GRID</b> 315K
PDF <b>WARRANTY - 10 YEAR LIMITED FOR CEILING INSTALLATION SYSTEMS</b> 83K
 <b>PRINT PRODUCT SPECS</b>

## What's in the Box?

<b>Standard Packaging</b>	20 piece(s) per carton 240 linear feet per carton
---------------------------	--